

Materials for technical room

Product	Quantity
Compacted crushed stone backfill (20cm)	6.0 m³
Extruded polystyrene (5cm) (underneath the floor planking)	33.0 m²
PVC foil (underneath the floor planking)	35.4 m²
Levelling concrete C8/10	0.6 m³
Simple concrete C12/15	4.8 m³
C25/30 reinforced concrete (support beams)	4.9 m³
Formwork (support beams)	40.7 m²
S500c reinforcement (support beams)	260.0 kg
C25/30 reinforced concrete (floor planking)	3.5 m³
S500c reinforcement (floor planking – jacks +rebars)	90.0 kg
SPPB Ø5/100/100 reinforcement (floor planking)	43.0 m²
C25/30 reinforced concrete (pillars)	1.6 m³

Product	Quantity
Formwork (pillars)	20.9 m²
S500c reinforcement (pillars)	460.0 kg
C25/30 reinforced concrete	2.8 m³
Formwork	28.4 m²
S500c reinforcement	337.5 kg
C25/30 reinforced concrete	4.1 m³
Formwork	32.8 m²
S500c reinforcement	491.4 kg
8x15cm timber	75.6 m
15x15cm props and wedges	11.8 m
15x15cm sill	24.0 m
Revetment (h= 18mm)	46.1 m²